

BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE-B


NAME OF THE WORK: Construction of culverts at Soundarya layout Vishveshwaraiah layout Manjunatha Nagara Defence colony and Vijaya Lakshmi layout Bagalagunte In ward no. 14

Sl. No	Description of work	Unit	Qty	Rate Quoted by Sri. K.Jagadish	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per the direction of Engineer-in-charge of the work	Cum	198.00	76.45	Rupees Seventy Six and Forty Five Paise Only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	29.70	4537.36	Rupees Four Thousand Five Hundred Thirty Seven and Thirty Six Paise Only
3	Providing and constructing granite/trap/basalt size stone masonry in foundation in cement motor 1:6, Stone hammered dressed in courses not less than 20 cms high. Bond stones at two m apart in each course including cost of materials, labour, curing including cost of materials, labour, curing complete as per specifications complete as per the direction of Engineer-in-charge of the work	Cum	112.05	3903.41	Rupees Three Thousand Nine Hundred Three and Forty One Paise Only
4	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Sqm	108.00	91.36	Rupees Ninety One and Thirty Six Paise Only



Signature of the Contractor


Executive Engineer

5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications, complete as per the direction of Engineer-in-charge of the work	Sqm	90.00	273.16	Rupees Two Hundred Seventy Three and Sixteen Paise Only
6	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC Cement @220 kgs with 20 mm and down size graded granite metal coarse aggregates @ 0.84 cum and fine aggregates @0.56 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well comated, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per , complete as per the direction of Engineer-in-charge of the work	Cum	8.10	4924.25	Rupees Four Thousand Nine Hundred Twenty Four and Twenty Five Paise Only
7	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. complete as per the direction of Engineer-in-charge of the work	Cum	108.90	5072.48	Rupees Five Thousand Seventy Two and Forty Eight Paise Only
8	Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. for TMT Bars Fe 500 complete as per the direction of Engineer-in-charge of the work	tone	9.80	52253.73	Rupees Fifty Two Thousand Two Hundred Fifty Three and Seventy Three Paise Only
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per the direction of Engineer-in-charge of the work	Cum	198.00	71.06	Rupees Seventy One and Six Paise Only



Signature of the Contractor



Executive Engineer